


SCHEDULE - B

Name of the Work: Construction of SSM drain from 1st Main Road to Solid Waste management centre in parallel road of SWD in Ward No. 18
Item No. 02

Sl. No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
1	KSRB 2-2-2 Earthwork excavation for foundation of building, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ~~hard~~ soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m after breaking of clods complete as per specifications. specification No. KRS 2.1(b) / 2.3.5	180.00	Cum	151.74	Rupees One Hundred Fifty One And Paise Seventy Four Only
2	KSRB 4-1-3 Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KRS 4.1.4.2	45.00	Cum	4290.80	Rupees Four Thousand Two Hundred Ninety And Paise Eighty Only
3	KSRB 5-4-3 Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:6, edges of stones chisel dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications. KRS 5.1.13	155.70	Cum	4423.70	Rupees Four Thousand Four Hundred Twenty Three And Paise Seventy Only
4	KSRB 4-1-6 Providing and laying in position plain cement concrete of mix M15 with cement @ 240kgs with 20mm and down size graded granite metal, coarse aggregate @ 0.878cum and fine aggregate @ 0.459 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. (P-12, It.4.5)	28.35	Cum	4779.00	Rupees Four Thousand Seven Hundred Seventy Nine Only
5	KSRB 15.1.3 Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	459.00	Sqm	79.90	Rupees Seventy Nine And Paise Ninety Only

Sl. No	Description of item	Quantity	Unit	In figures	In words	Rate (Rs)
6	Providing and laying position reinforced cement concrete covering slabs madeout of mix 1:1.5:3 with 20mm and down size granitemetal mixed concrete laid in layers not exceeding 15cms vibrated including cost of materials, labour curing providing and laying in position including transportation complete as per specifications Approved Daty Rate	375.30	Sqm	1427.15	Rupees One Thousand Four Hundred Twenty Seven And Paise Fifteen Only	
7	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc. complete. Of size 450 x 200 x 400mm	565.00	Nos	316.45	Rupees Three Hundred Sixteen And Paise Forty Five Only	
8	KSRRB 800-1: Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8	76.50	Sqm	51.84	Rupees Fifty One And Paise Eighty Four Only	
9	Cost of Haulage excluding loading and unloading MORTH chapter 1 (Lead Chart enclosed) (for 10 kms)	180.00	Cum	94.82	Rupees Ninety Four And Paise Eighty Two Only	


Executive Engineer-1
 KRIDL, BBMP, Bangalore.


 Executive Engineer (H)
 Bruhat Bangalore Mahanagara Palike